BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/OW/WORK_INDENT16516

APPROVED SCHEDULE - B

EE/BTM/BBMP/E-PMT/10/2014-15, Date: 21.02.2015

Improvements and asphalting to canara bank layout cross roads in ward no. 09 of Vidyaranypaura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B B UMESHA	
				In Figures	In Words
1	266.33	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	105.84	Rupees One Hundred Five and Eighty Four Paise Only
2	429	Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	58.32	Rupees Fifty Eight and Thirty Two Paise Only
3	429	Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	75.6	Rupees Seventy Five and Sixty Paise Only
4	1507.5	Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet/surface dressing and stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work	Sqm	46.44	Rupees Forty Six and Forty Four Paise Only
5	226.13	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1500.0	Rupees One Thousand Five Hundred Only
6	1507.5	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	12.2	Rupees Twelve and Twenty Paise Only
7	1507.5	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	35.21	Rupees Thirty Five and Twenty One Paise Only

8	37.69	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen, etc complete as per specifications and directions of engineer in charge of the work	Cum	12000.0	Rupees Twelve Thousand Only
9	266.33	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	72.71	Rupees Seventy Two and Seventy One Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92